



2
DETAIL PLAN AT HOUSE
1"0" = 20'0"
NORTH

1
SITE UNDERGROUND
& FENCING PLAN
MIDDLE AREA OF SITE
NORTH

KEY

- NEW UNDERGROUND LINES (TYP)
- NEW AND/OR REPLACED SPLIT RAIL FENCE (TYP)
- ① ELECTRICAL LINE FROM HOUSE TO POWER POLE ACROSS RIVER VIA TRANSFORMER & BRIDGE
- ② WATER, SECURITY & PHONE FROM HOUSE TO GARAGE
- ③ RUN FOUNDATION DRAINS AT HOUSE & GARAGE TO DAYLIGHT
- ④ NEW WATER & ELEC. LINE FROM WELL TO HOUSE (FINAL LAYOUT BY SUBCONTRACTOR)
- ⑤ PUMPED SEPTIC LINE FROM HOUSE SEPTIC TANK TO DISTRIBUTION BOX
- ⑥ PROPANE LINE FROM HOUSE TO L.P. TANK
- ⑦ HOUSE SEPTIC TANK (SEE DWGS BY CHURCH)
- ⑧ BURIED PROPANE TANKS FOR HOUSE & BARN
- ⑨ ELECTRIC & SECURITY LINES FROM HOUSE TO ENTRY GATE
- ⑩ DISTRIBUTION BOXES & SEPTIC FIELDS FOR HOUSE AND BARN
- ⑪ PUMPED SEPTIC LINE FROM BARN SEPTIC TANK TO DISTRIBUTION BOX
- ⑫ BARN SEPTIC TANK (SEE DWGS BY CHURCH)
- ⑬ FRENCH DRAIN & DRYWELL (SEE DWG A2.2)
- ⑭ SECURITY & PHONE FROM HOUSE TO BARN
- ⑮ ELECTRICITY FROM NEW TRANSFORMER TO BARN
- ⑯ WATER FROM HOUSE TO BARN (VERIFY W/ PLUMBER)
- ⑰ PROPANE LINE FROM BARN TO L.P. TANK
- ⑱ ELECTRICAL FROM TRANSFORMER TO GARAGE

1" = 40'0" UNL

NOTES: A. SEE DWG A2.5 FOR UNDERGROUND & FENCE WORK AT FUTURE GUEST HOUSE AND FESTIVITY GROUNDS AT SOUTH END OF PROPERTY.
B. VERIFY ALL UNDERGROUND WORK WITH PROPER DESIGNERS AND SUBS PRIOR TO DIGGING.